

# PROJECT DETAILS

**Client:** Scottish Water

**Site:** Rothesay

**Application:**

- Prompt installation of a temporary carbon filter following critical damage to the original OCU
- Design, supply, installation and commissioning of a new replacement OCU
- Two stage OCU achieves  $<500 \text{ ou}_E/\text{m}^3$  at stack
- Flowrate  $11,500 \text{ m}^3/\text{hr}$

**Equipment:**

- PVC/GRP bio-trickling filter
- Access platform
- PVC/GRP carbon filter
- Duty/Standby fans
- Interconnecting ductwork and supports
- Instrumentation

**Year delivered:** 2023



New ERG odour control system



Slab before replacement equipment is installed. Emergency carbon filter supplied by ERG keeps the works functional



Temporary filter reduces plant downtime after existing equipment was fire damaged



[www.ergapc.co.uk](http://www.ergapc.co.uk)